

BRUHATH BANGALORE MAHANAGARAPALIKE

YELAHANKA ZONE

PRE MEASUREMENTS

Name of work: Maintenance of Existing Borewells in ward No. 05 Byatarayanapura Sub Division.

Work Order No: BBMP/EE/BTP/WO/50/2019-20 dt: 10-07-2019

OB NUMBER: 005-20-000040


Estimate Cost: 30 00 lakhs.


As No: AS/CE(YNK)/08/2019-20 dt: 09-05-2019

Ts No: TS/CE(YNK)/04/2019-20 dt: 09-05-2019


Name of Contractor : Sri. B Girish


SI No	Description of item	Unit	No	L	B	D	Qty
43	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P NO - 6 I NO - 2 3. PWD SR 18-19)						
	Venkateshwara layout 2nd Cross	Cum	1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	18 00	0 45	0 75	6 08
	Venkateshwara layout 3rd Cross		1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	10 00	0 45	0 75	3 38
	Venkateshwara layout 4th Cross		1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	12 00	0 45	0 75	4 05
	Kattigenahalli Main Road		1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	30 00	0 45	0 75	10 13
			1	10 00	0 45	0 75	3 38
	Kattigenahalli 2nd Main Near Overhead Tank		1	24 00	0 45	0 75	8 10
				Actual Qty			338 85
				Qty Limited to			337.50


 Assistant Engineer
 Ward No.05
 Byatarayanapura Sub Division


 Asst. Executive Engineer
 Byatarayanapura Sub Division
 Bangalore-24

No	Description of item	Unit	No	L	B	D	Qty
1	Providing and installing at site of work 63mm (0 662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe around to a depth not less than 15cms with gravel or selected earth available from the excavation etc complete (P NO - 96, I.NO - 13.73 2, PWD SR 18-19) 75 mm dia 6 KSC PVC pipe						
	Venkateshwara layout 2nd Cross		1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	18 00			18 00
	Venkateshwara layout 3rd Cross		1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	10 00			10 00
	Venkateshwara layout 4th Cross		1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	12 00			12 00
	Kattigenahalli Main Road		1	30 00			30 00
			1	30 00			30 00
			1	30 00			30 00
			1	10 00			10 00
			1	24 00			24 00
	Kattigenahalli 2nd Main Near Overhead Tank						1004 00
							1000.00
						Actual Qty	
						Qty Limited to	


 Assistant Engineer
 Ward No.05
 15/7/20


 Engineer
 By
 15/7/20